Welcome to the third webinar in the series 'how to make the ground work for you'

www.roger-bullivant.co.uk

Info@roger-bullivant.co.uk



in @rogerbullivantlimited

How precast foundations can improve your build

Topics include reducing programme, ground levels and modular housing.

Andrew Preece Business Unit Manager– South West

Richard Taylor Business Unit Manager – Midlands



Contents

- 01 Our Business
- **02** Reviewing the engineering process
- 03 Offsite manufacture
- **04** Installation process
- 05 Questions








Our Business











About RB









Years of experience...



PILING



GROUND IMPROVEMENT




FOUNDATIONS



RESTRICTED ACCESS



Expertise in...





<u>02</u>

Reviewing the engineering process



Engineering Process

Project Review

Site Investigation

Loadings and load types


Environment

Preliminary Solution

Preliminary Design

All Sectors

Final foundation solution and final design





Select a support system

Driven Precast Concrete Piles

Driven Steel Tube Piles

Replacement CFA

Displacement CDA

Mini / Restricted access Piles





Modern Methods of Construction

Select an RB precast concrete beams system

Category 3 – Pre-Manufacturing – Non-systemised structural components

Produces a flexible modular foundation

Factory quality and safety

Reduced on site program

In house design team from concept to completion to work with your engineering team







Off site Manufacturing








Installation Process







Precast RBeam







Modular Foundations

Project- Private Housing Development, Stoke-on-Trent St Modwen Homes

Key issues/requirements

- Brownfield site
- Obstructions
- Site to be uplifted / capped
- Volume build program

- Driven Piles
- Pre agreed strategy on obstructions
- Precast beams scheduled delivery





School Building

Project- Melksham Oak Community School – New Teaching Block

Key issues/requirements

- Steel frame
- Quick Program
- Adjacent existing school
- Residential location
- Delivery restrictions

- 177 (250) Precast Driven Piles (Quiet hammer)
- 280Im precast RBeam
- 70No Holding down bolts for steel frame





Care home

Project- TRL Site, Crowthorne

Key issues/requirements

- Steel frame / Traditional mix
- Lift pit slabs / Crane base
- Holding Down Bolt sets
- Quick Program
- Residential location

Project Solution

- 186 (200), 120 (250) & 46 (300)Precast Driven Piles (Quiet hammer)
- 300 SFA pile for Crane base
- 3400lm pile in 10 days
- 750lm precast RBeam in 7 weeks
- Holding down bolts for steel frame



• Lift pit bases



Care home

Project- TRL Site, Crowthorne

Key issues/requirements

- Steel frame / Traditional mix
- Lift pit slabs / Crane base
- Holding Down Bolt sets
- Quick Program
- Residential location

- 186 (200), 120 (250) & 46 (300)Precast Driven Piles (Quiet hammer)
- 300 SFA pile for Crane base
- 3400lm pile in 10 days
- 750lm precast RBeam in 7 weeks
- Holding down bolts for steel frame
- Lift pit bases





Retaining base/wall and house all combined Project- Woolhampton

Key issues/requirements

- Insitu Concrete Retaining wall
- Insitu piled slab
- Integrated with Precast Foundation
- Quick Program
- Residential location

- 300 x 300 Precast Driven Piles for walls & 200 x 200 for plots (Quiet hammer)
- 150lm of wall and base
- Integrated with Precast Foundation system
- Maximum retained height 3.25m





Retaining base/wall and house all combined Project- Woolhampton

Key issues/requirements

- Insitu Concrete Retaining wall
- Insitu piled slab
- Integrated with Precast Foundation
- Quick Program
- Residential location

- 300 Precast Driven Piles for walls & 200 for plots (Quiet hammer)
- 150lm of wall and base
- Integrated with Precast Foundation system
- Maximum retained height 3.25m



Thank you for listening

www.roger-bullivant.co.uk

Info@roger-bullivant.co.uk



in @rogerbullivantlimited

