Welcome to the first webinar in the series

# www.roger-bullivant.co.uk

☑ Info@roger-bullivant.co.uk



**in** @rogerbullivantlimited



#### **Designing Foundations for YOU**

# www.roger-bullivant.co.uk


Andrew Preece South West Area Manager

Nigel Rake MSc IEng AMIStructE CMgr MCMI Foundation Systems Technical Manager



### <u>Contents</u>


- Our Business
- Our Client and the Project
- Information available at tender stage
- 04 Tender process
- Design input to final solution
- Q&A






# Our Business






















## Years of experience...



PILING



GROUND IMPROVEMENT



FOUNDATIONS



RESTRICTED ACCESS



## Overview

Our Client – Nicholas King Homes established in 1991 who predominantly work in the Home Counties and the SE of England. Founder and Chairman Nicholas King is still as much part of the day to day running of the company.

The project is a joint venture with Nicholas King Homes and A2 Dominion.

The project is the Waters Edge Development, Mytchett which is a new development of 248No properties consisting of 3, 4, 5 bed houses and 2 Bed Apartments. The development is surrounded by beautiful lakes with over 2.5k of waterside walks.

Two main phases North & South.





## Site investigation by RSK

Over view on the site which was being remediated to create a 'working platform' 600mm below FFL.

Varying made ground from 0.5m and 3.6m

Overlying River terrace Gravels from 1.7m to 3.7m

Over Camberley Sand Formation from 5.1m to 9.0m to depths of 16.0m to 19.5m

CFA piles were originally specified and estimate submitted

Alternative Segmental RBL Precast Driven Pile (Displacement over replacement)



#### Nicholas King Homes PLC

#### Waters Edge, Mytchett

Supplementary Geoenvironmental and Geotechnical Site Investigation

29116-R02 (01)

AUGUST 2019





## **Roger Bullivant submission**

Following dialogue with NKH we put forward two options initially

Compliant option - CFA piles up to maximum 11.0m founding in the Camberley Sands formation and the RBL RBeam Precast Foundation package contract sum in the order of £1.965M

Alternative option – Precast Piles (4.0m to 8.0) and the RBL RBeam Foundation Precast Contract sum £1.6M

Massive saving in time on site and speed of delivery

No spoil arisings for pile installation

Accurate off site manufactured Precast Foundation System





# Roger Bullivant design considerations

The building construction, traditional, timber frame or A N Other

Preliminary drawings, take off of pile numbers and loadings and quantities of insitu concrete for pile caps or precast caps and beams

Site conditions, type of pile, size and depth

General assessment of time on site, the piles (size and depths) type of Precast beam and meterage



Testing requirements to satisfy Premier (Warranty Provider) which was Static Load test 1:100 piles (28No allowed) with a caveat that these could be reduced following satisfactory results



# Roger Bullivant Ltd – negotiation

RBL submitted two options which clearly identified that the alternative option was a more cost effective way forward for the client.

Final numbers would be subject to receipt of construction drawings, engineering layouts, load take downs and sequence of works.

Works were scheduled with phases agreed, number of visits and start dates agreed.






# Design Process












# B




# AB

1902: Waters Edge, Mytchett	HOUSE TYPE AREAB3(A) - M* = 93.32 m* Ft* = 1004.48 m*B4(A) - M* = 117.18 m* Ft* = 1261.31 R*
House Types B3(A) & B4(A) (BLK18) Plots 58 - 59	Timber FramerMasonry Construction
DRAWINGS:         Dwg No       Title:         B3(A)_B4(A)_100_Sub_58-59 B3(A)_B4(A)_102_Graf_58-59 B3(A)_B4(A)_102_Graf_58-59 B3(A)_B4(A)_102_Graf_58-59 B3(A)_B4(A)_102_Graf_58-59 B3(A)_B4(A)_202_Frant_58-59 B3(A)_B4(A)_A0_A BA(A)_A0_Frant_50 B3(A)_B4(A)_A0_A BA(A)_A0_Frant_50 B3(A)_B4(A)_A0_A BA(A)_A0_Frant_50 B3(A)_B4(A)_A0_A BA(A)_A0_Frant_50 B3(A)_B4(A)_A0_A BA(A)_A0_Frant_50 B3(A)_B4(A)_A0_A BA(A)_A0_Frant_50 B3(A)_B4(A)_A0_BA(A)_A0_Frant_50 B3(A)_B4(A)_A0_A BA(A)_A0_Frant_50 B3(A)_B4(A)_A0_A BA(A)_A0_Frant_50 B3(A)_BA(A)_A0_Frant_50 B3(A)_BA(A)_A0_Frant_50 B3(A)_BA(A)_A0_Frant_50 B3(A)_BA(A)_A0_Frant_50 B3(A)_BA(A)_A0_Frant_50 B3(A)_BA(A)_A0_Frant_50 B3(A)_BA(A)_A0_Frant_50 B3(A)	Tenure HOUSING ASSOCIATION SHARED OWNERSHIP THIS HOUSE PACK HAS BEEN CROSS CHECKED AGAINST INFORMATION RECEIVED FROM THE FOLLOWING Structural Engineer Ground Floor Sub-Contractor Joist Manufacturer Truss Manufacturer Staircase Supplier Kitchen Designer Ventilation Designer
B3(A)_B4(A)_500_Gnd_First_Serv_58-59 Services Drawings to be read in conjunction wth Block Plans, Elevations & Technical Specification	WATERS EDGE HOMES FLC
	Botton V2 Owner Nicholas King Homes Maters Edge Genetic Day Io. Review Mytchett II. In Advances Ionning Cover Avances Vittigethdate/betweene.vits avance.res














AB

Job	H 19 0020	CREATE FILE LISTS		REMEDIALISSUE		FILE REPO	RTER		292	238	
HOUSE T	PE(S) ADD PLOT NO(S)		) / INSITU	HANDING(S) / REF.		TANKING	HEAVE	FLOOR	DWG NO.	CALCULATION NO.	\
3 C3	17g	DBG			N	N	YES		283	232	1
3(A) C3(A)	18	ES			Y	N	YES		217 - 21		
54 C4	18g	DBG			N	N	YES		283	232	_ \
C4(A) C4(A) D3 D3	19	E4 SNG			Y N	Y	NO	-	219 - 2	20 204	- \
D3 D3 D3(A) D3(A)	19g 20	D4v3			N	N	YES		221 -		- \
24 D4	20g	DBG			N	N	YES		283	232	- \
24v1 D4v1	21	D4v3			N	N	YES		223 -	224 207	_ \
04v2 D4v2	21g	DBG			Y	N	YES	10 A	287	236	
04v3 D4v3	22	D4v2			N	N	NO		225 -	the second se	
24v4 D4v4	23	D4			N	Y	YES		227 -		
25 D5 13 E3	23g - 24g 24	TWG H4			N	N	YES YES	2	288	- 230 23	10
13 E3 14 E4	24 25 - 26	M3 M3			N	N	YES				11
5 ES	27 - 28	G3 G3			N	N	YES	9			212
F1 F1		M3 M3			N	N	YES				213
=1(A) F1(A)		H4v			Y	N	YES			- 238	214
F2 F2	32	85			Y	N	YES		239	- 240	215
F2(A) F2(A)	33	L4			N	N	YES		241	- 242	216
2v F2v	34 - 35	(4 K4			N	N	YES	į),	243	3 - 244	217
-3 F3	36 0	4			N	Y	YES	11	24	5 - 246	209
=3(A) F3(A)	36g SN	IG			N	N	YES		28	34	235
=4(A) F4(A)	37 - 38 G	3 G3			N	N	NO		2	47 - 248	218
5(A) F5(A)	39 - 40 C	3 C3			N		YES		2	49 - 250	219
_3 G3	41 A4v	1			N	1 1	YES			251 - 252	220
5 G5	42 E4				1		NO NO			253 - 254	204
14 H4	43 K4v				_	_	NO NO			255 - 256	1
					_	_		ACEON			1
14v H4v	44 - 46 A4v2	2 A4v2 D4v4				_	N PLOT 46 & GAP		×	257 - 258	-
3 ]3	47 - 52 F3				_	-	N YES			259 - 260	1
4 J4	53 - 55 N3	N3 N3				Y	Y YES	5		261 - 26	2 22
K3	56 - 57 B3(A)	B3(A)				N	N YE	S		263 - 26	54 22
K4	58 - 59 B3(A)	B4(A)				N	N YE	s		265 - 2	66 2
1 K4v1	60 - 62 D3(A)	D3(A) D3(A)			_	N	N YE	ES		267 - 2	268 2
K4v2	63 - 64 D3(A)	D3(A)				N	N N	10		269 -	270
L3	65 C4(A)					N	NP	10		271 -	272
L3v	66 C4(A)					N	N	NO		273 -	274
L4	67 - 68 D3(A)	D3(A)				N	N	NO		275 -	276
МЗ	188 - 190 A3v	K3 A3v				N	N	NO		277 -	278
M4	191 - 192 G3	G3				Y	N	NO		279 -	- 280
N3	193 - 194 G3	G3				N	N	NO		281	- 282




Job DH 19 0020	PRINT PLOTLIST		PCO ISSUE	OPEN	PROJEC	FOLDER	1	292	238	
	PRINTTICKSHEETS	S PRODUCTION ISSUE	REMEDIALISSUE	F	ILE REPO	RTER		LJL	256	
HOUSE TYPE(S) ADD	PLOT NO(S). ADD HO	USE TYPE(S) / INSITU	HANDING(S) / REF.	UNDER- BUILD	TANKING	HEAVE	FLOOR	DWG NO	CALCULATION NO.	\
<mark>3 C</mark> 3	17g DBG			N	N	YES		283	232	1
23(A) C3(A)	18 E5			Y	N	YES		217 -		
54 C4	18g DBG			N	N	YES		283	232	- \
24(A) C4(A) 23 D3	19 E4 19g SNG			Y N	N	NO	1	219 -	220 204	- \
D3(A) D3(A)	20 D4v3			N	N	YES			222 207	- \
24 D4	20g DBG			N	N	YES		283	232	- \
04v1 04v1	21 D4v3			N	N	YES		223 -	224 207	_ \
DAV2 DAV2 DRAWING	is and the second s		ICALC	s					236	
	0 RBL TYPICAL SECTION	VS FL DR X 100	DH 19	9 0020 F	BL PT	1-9(HTF1(A))_FL_PC	X 201		208	
	RBL_PT1-9(HTF1(A))_FL		DH 1	9 0020_F	RBL_PT	10-11(HTM4,M4)_FL	PC_X	202	209	
	_RBL_PT10-11(HTM4,M4)					12,15(HTD4v1)_FL_F			23	
	_RBL_PT12(HTD4v1)_FL_					13,14,19,42(HTE4)_			21	
	_RBL_PT13(HTE4)_FL_DF RBL_PT14(HTE4)_FL_DF					16,17(HTD5)_FL_PC 18(HTE5) FL PC X		5	2	
DU 10 0020	RBL_PT15(HTD4v1)_FL_0					20,21(HTD4v3)_FL		207		12
	RBL PT16(HTD5) FL DR					[22(HTD4v2) FL PC				213
-1(A) F1(A) DH 19 0020 B	RBL PT17(HTD5) FL DR					123,36(HTD4) FL P				214
F2 F2 DH 19 0020 R	BL PT18(HTE5) FL DR					T24(HTH4)_FL_PC				215
	BL PT19(HTE4) FL DR					T25-26(HTM3,M3)			1	216
2v F2v DH 19 0020 RE	BL_PT20(HTD4v3)_FL_DI	R X 221-222	DH 1	9 0020	RBL_P	T27-28(HTG3,G3)_	FL_PC	X 212		217
F3 DH 19 0020_RE	BL_PT21(HTD4v3)_FL_DF	R_X_223-224				T29-30(HTM3,M3)_				209
-3(A) F3(A) DH 19 0020_RB	L_PT22(HTD4v2)_FL_DF	R_X_225-226	DH 1	9 0020	RBL_P	T31(HTH4v)_FL_P0	C_X_21	14		235
4(A) F4(A) DH 19 0020_RBI	L_PT23(HTD4)_FL_DR_	X 227-228	DH 1	9 0020	RBL F	T32(HTB5)_FL_PC	X 21	5		218
	PT24(HTH4) FL DR )	229-230	DH 1	9 0020	RBL F	T33(HTL4) FL PC	X 21	6		219
G3 DH 19 0020_RBL	PT25-26(HTM3,M3) F	DR X 231-232	DH 1	9 0020	RBL F	PT34-35(HTK4,K4)	FL P	C X 217		220
	PT27-28(HTG3,G3) FL	DR X 233-234	DH 1	9 0020	RBL F	PT37-38(HTG3,G3)	FLP	C X 218	3	-
5 G5 DH 19 0020 RBI	PT29-30(HTM3,M3) FL			and the second se		PT39-40(HTC3,C3)		the second s		204
	PT31(HTH4v) FL DR )			the fact that the second se		PT41(HTA4v1) FL				221
14	PT32(HTB5) FL DR X			and the second se		PT43(HTK4v1) FL	and the second se	the second se		22
	PT33(HTL4) FL DR X					PT44-46(HTA4v2,			DC X 222	22
				and the second second second second second second	the second second second			and the second	FUALLE	2
	PT34-35(HTK4,K4)_FL_					PT47-52(HTF3)_F				
	T36(HTD4)_FL_DR_X_			and some the second second second second second	and a second second second second	PT53-55(HTN3,N3	And the second sec	and the second se		2
K4 K4 DH 19 0020_RBL_P	T37-38(HTG3,G3)_FL_	DR_X_247-248	DH 1	19 0020	_RBL_	PT56-57(HTB3(A)	),B3(A	())_FL_P	C_X_225	
K4v1 K4v1 DH 19 0020_RBL_PT	T39-40(HTC3,C3) FL [	DR X 249-250	DH 1	19 0020	RBL	PT58-59(HTB3(A	),B4(A	)) FL F	PC X 226	
	41(HTA4v1) FL DR X	251-252	DH 1	19 0020	RBI	PT60-62(HTD3(A	DBU	A) D3(A)	FI PC X 22	7
DH 10 0020 DBL DT		Experience of the second se				PT63-64,67-68(H				
10 10										20
3v L3v DH 19 0020_RBL_PT4	na hanna a shekari sa baran karan	and the second state of th				_PT65,66(HTC4(#				
DH 19 0020 RBI PT4	4-46(HTA4v2,A4v2,D4	4v4)_FL_DR_X_257-	258 DH 1	19 0020	RBL	_PT188-190(HTA	3v,K3	,A3v)_F	L_PC_X_230	
4 L4 DH 19 0020_RBL_PT4	7-52(HTE3) FL DR X	259-260	DH	19 0020	) RBI	PT191-192,193	-194(	ITG3.G	3) FL PC X 2	31
								Contraction of the second second		
4 M4 DH 19 0020_RBL_PT53						_PT12g,15g,17g	and the second se	and a second	and a standard standa	232
DH 19 0020 KBL P156	6-57(HTB3(A),B3(A))_	FL_DR_X_263-264				_PT13g-14g(HTE				
N3 DH 19 0020 RBL PT58-	-59(HTB3(A), B4(A))	FL DR X 265-266	DH	19 0020	0 RBI	PT16g(HTDBG	) FL	PC X	234	
N4 DH 19 0020_RBL_PT60-						_PT19g,36g(HT				
DH 19 0020 RBL PT63-0						PT21g(HTDBC				
DH 19 0020 RBL PT65(H	11C4(A)) FL DR X	2/1-2/2	DH	19 002	0 RB	L PT23g-24g(HT	IWG	FL P	C X 231	




	DH 19 0020	EATE FILE		OPEN PROJECT FOLDER	292 23	38		
/		PRODUCTION ISSUE	REMEDIAL ISSUE	FILE REPORTER	CALC	ULATION		
	TPE(S) ADD INCO TO CARACESI ADD	HOUSE TYPE(S) / INSITU	HANDING(S) / REF.	UNDER TANKING HEAVE FLOOR		NO.		
3 C3 (3(A) C3(A)	17g DBG 18 E5				100000000000000000000000000000000000000			
14 C4	18g DBG		RD www.ro	ger-bullivant.co.uk	HOUSE FOUR	NDATIONS PRECAST DES	IGN CHECKLI	ST
24(A) C4(A) 23 D3	19 E4 19g SNG	Proje	ect Name:	MYTCHETT WE (VISIT 2)	Contract No:	DH/19/0020		
D3(A) D3(A)	20 D4v3		House Type:	PT58-59(HTB3(A),B4(A))	Drawing No(s):	265-266		<b></b>
24 D4 24v1 D4v1	20g DBG 21 D4v3		nouse type.		browing tro(s).	Construction of the second		
24v2 D4v2	DRAWINGS			INITIAL DESIGN & CHECK			D	C/E
04v3 D4v3	DH 19 0020_RBL_TYPICAL SEC		ork layout			Drawn CAD V	1	
24v4 D4v4	DH 19 0020_RBL_PT1-9(HTF1(A) DH 19 0020_RBL_PT10-11(HTM4		lly check overall ext	ernal dims				~
13 E3	DH 19 0020_RBL_PT10-T1(HTM4 DH 19 0020_RBL_PT12(HTD4v1)		ly check internal roo	om (wall to wall) dims				~
54 E4	DH 19 0020_RBL_PT13(HTE4)_FL			or grid offsets / beam types etc.				
5 <b>E</b> 5	DH 19 0020_RBL_PT14(HTE4)_FL DH 19 0020_RBL_PT15(HTD4v1)_FL	I DR V 211		orientation & handing. Add "FRONT" note.	Reference landsc	ape features?		$\downarrow \checkmark \downarrow$
1 F1	DH 19 0020_RBL_PT16(HTD4VI)_I	DR X 213-2	ors & roof specifica	tion				
	DH 19 0020_RBL_PT17(HTD5)_FL	DR_X_215-2 Identify lo	ad bearing walls					1~
	OH 19 0020_RBL_PT18(HTE5)_FL_		indows / porch slat	os / chimney / other slabs required?		Yes No 🗸	1 1	1
	0H 19 0020_RBL_PT19(HTE4)_FL_ H 19 0020_RBL_PT20(HTD4v3)_FI		id lines & labels					1 ~
	1 19 0020_RBL_PT20(HTD4v3)_FL		grid dimensions				1 ~	1 ~
	19 0020 RBL PT22(HTD4v2) FL		d floor span direct	ions				
	19 0020_RBL_PT23(HTD4)_FL_D		lations, produce I	ine loads & insitu cap reinforcement chec	ks			
5(A) F5(A) DH	19 0020_RBL_PT24(HTH4)_FL_D		sed beam spans &	beam type				
G3 DH 1	19 0020_RBL_PT25-26(HTM3,M3	Produce draft	t layout showing p	iles, beams & insitu –discuss with altern	ative engineer if	f required		<u> </u>
	9 0020_RBL_PT27-28(HTG3,G3) 9 0020_RBL_PT29-30(HTM3,M3)			against take-off – discuss with area office		-	- t ž	
	0020 RBL PT31(HTH4v) FL D		nd beam layout				+	
	0020 RBL PT32(HTB5) FL DF	2 X 2					<u> </u>	1~
	0020 RBL PT33(HTL4) FL DR	X 2	ientation (Tee Be					
	0020 RBL PT34-35(HTK4,K4)	Are drainage he	eams required (Te	e Beam)		Yes No		
кз Кз DH 19 0	020_RBL_PT36(HTD4)_FL_DR	X_2 Add void former	r to perimeter be	ams for heave? Add heave note. Use "	VOIDFORMER"	command		~ \ ~
K4 K4 DH 19 0	020_RBL_PT37-38(HTG3,G3)_	FL_ Add 3D drain rur	ns "DRAINRUN" o	ommand				V 1.
	020_RBL_PT39-40(HTC3,C3)_F		els (TOB) - Do be	am levels need to be adjusted for drai	nage?	Yes 🗸 No		V I
	20_RBL_PT41(HTA4v1)_FL_D	R_ Change and the		m types (T5 / Section 4 RBeam)			- 1	v t
DH 19 002	20_RBL_PT42(HTE4)_FL_DR_ 20_RBL_PT43(HTK4v1)_FL_DF						-	. 1
3V L3V DH 19 002	0 RBL PT44-46(HTA4v2,A4v2		ate tables / Dila	& Beam schedule tables				<del>÷ †</del>
<sup>4</sup> L4 DH 19 0020	RBL PT47-52(HTF3) FL DI			a beam schedule tables				<u> </u>
M3 DH 19 0020	_RBL_PT53-55(HTN3,N3,N3)	Complete calculation					-	~ 1
M4 DH 19 0020	_RBL_PT56-57(HTB3(A),B3(	Insitu caps & slab n	otes					~
	RBL_PT58-59(HTB3(A),B4(	Complete all section	marks					$\checkmark$
	RBL_PT60-62(HTD3(A),D3	Update general note	s / title block				1	$\checkmark$
	RBL_PT63-64(HTD3(A),D3	Fill out all references	used					
DH 19 0020_R	RBL_PT65(HTC4(A))_FL_[							

































Client:		HOLAS KING HOMES		By:	LK	Engineer:	JLS	
Project:		CHETT WE (VISIT 2)				-		
Project No.		19/0020		Date:	JUNE 20	Sheet No.	2	
Plot:	58-5	9 HT B3(A), B4(A)						
Title:	Lin	e Loads		Rev:		Doc. No:	226	
	ENGIN	EERS LOADS PROVIDED B	Y RSK REF: 133656 SK01 - SK	48				
Grid Reference:	Load Case		ther Dead	Self Weight	Total Live	Total Dead	Design SLS	Design ULS
		Live						
				1				E 1 00
	1	4.0	30.0	4.00	4.00	34.00	38.00	54.00
	1	4.0 2.0	30.0 37.0	4.00 4.00	4.00 2.00	34.00 41.00	38.00 43.00	54.00 60.60
	2	2.0	37.0	4.00	2.00	41.00	43.00	60.60
	2	2.0 8.0	37.0 48.0	4.00 4.00	2.00 8.00	41.00 52.00	43.00 60.00	60.60 85.60
	2 3 4	2.0 8.0 9.0	37.0 48.0 25.0	4.00 4.00 4.00	2.00 8.00 9.00	41.00 52.00 29.00	43.00 60.00 38.00	60.60 85.60 55.00
	2 3 4 5	2.0 8.0 9.0 8.5	37.0 48.0 25.0 45.0	4.00 4.00 4.00 4.00	2.00 8.00 9.00 8.50	41.00 52.00 29.00 49.00	43.00 60.00 38.00 57.50	60.60 85.60 55.00 82.20



RB Walton Park, Hearthcote Road, Swadlincote, Derbyshire DE11 9DU +44 (0)1332 977 300 • info@roger-bullivant.co.uk • www.roger-bullivant.co.uk

λt.	NICHOLAS KING HOMES	By:	ТК	Eng:	JLS
eot:	MYTCHETT WE (VISIT 2)	- Ug.	LIX	ung.	51.5
ect No.	DH/19/0020	Date:	JUNE 20	Sheet No.	
:	58-59 HT B3(A), B4(A)	Date:	JUNE 20	oneecito.	5
le:	Pile Table	Rev:	-	Doc. No:	226

PILE SIZE 200 sq 250 sq - sq MAXIMUM PILE LOAD 200 kN 350 kN - kN

						P	ILE LOAD	5				_	
Pile				Load					Add.	Equalis	ed with	TOTA	L (kN)
No.	Bm	Rn	Bm	Rn	Bm	Rn	Bm	Rn	Load	Pile	Adj.	1014	L (KN)
4	Q1-1	60	K1-1	46	T2-4	69						174	175
5	K1-1	46	U2-1	71	T2-4	69						185	200
6	U2-1	71	T2-3	108								179	200
7	L1-2	56	T2-2	77	R1-4	64						197	200
8	R1-4	64	T2-8	38	CC3-4	93						195	200
9	CC3-4	93	T2-5	103	L1-5	75						271	275
10	T2-4	69	L1-4	50								118	125
11	T2-4	69	T2-4	69								137	150
12	T2-3	108	T2-3	108								217	225
13	R1-7	77	L1-2	56								133	150
14	CC3-7	113	R1-7	77								190	200
15	Q1-1	60	CC3-7	113	L1-5	75						248	250
16	Q1-1	60	A1-3	30	L1-4	50						139	150
17	K1-2	53	A1-3	30								83	100
18	U2-2	80	K1-2	53	T2-4	69						202	225
19	T2-3	108	U2-2	80								188	200



RB Walton Park, Hearthcote Road, Swadlincote, Derbyshire DE11 9DU +44 (0)1332 977 300 • info@roger-bullivant.co.uk • www.roger-bullivant.co.uk

Client:	NICHOLAS KING HOMES	By:	LK	Eng:	JLS
Project:	MYTCHETT WE (VISIT 2)	Dy.		eng:	JLO
Project No.	DH/19/0020	Date:	JUNE 20	Sheet No.	
Plot:	58-59 HT B3(A), B4(A)	Date:	JUNE ZU	Sheet NO.	•
Title:	Beam Table	Rev:	-	Doc. No:	226

				Be	am Analysis				
Beam	Span	Load Case	Service Load (kN/m)	Ultimate Load (kN/m)	Beam Type	Minimum Section Type	Serv. Pile Rn. (kN)	Ult. Beam Rn. (kN)	Minimum Rqd. Cap Type
A1-3	1000	3	60.00	85.60	RBEAM_400	1	30	27	-
K1-1	2400	1	38.00	54.00	RBEAM_400	1	46	55	-
K1-2	2460	2	43.00	60.60	RBEAM_400	1	53	63	-
L1-2	2610	2	43.00	60.60	RBEAM_400	1	56	68	-
L1-4	2610	4	38.00	55.00	RBEAM_400	1	50	61	-
L1-5	2610	5	57.50	82.20	RBEAM_400	1	75	92	-
Q1-1	3150	1	38.00	54.00	RBEAM_400	1	60	75	-
R1-4	3360	4	38.00	55.00	RBEAM_400	1	64	82	-
R1-7	3360	7	46.00	65.80	RBEAM_400	1	77	98	-
R2-6	3360	6	51.00	73.20	RBEAM_400	2	86	109	-
T2-2	3580	2	43.00	60.60	RBEAM_400	1	77	97	-
T2-3	3610	3	60.00	85.60	RBEAM_400	2	108	138	-
T2-4	3610	4	38.00	55.00	RBEAM_400	1	69	89	-
T2-5	3580	5	57.50	82.20	RBEAM_400	2	103	132	-
T2-8	3580	8	21.00	30.20	RBEAM_400	1	38	48	-
U2-1	3730	1	38.00	54.00	RBEAM_400	1	71	90	-
U2-2	3730	2	43.00	60.60	RBEAM_400	2	80	102	-
CC3-4	4900	4	38.00	55.00	RBEAM_400	3	93	124	-
CC3-6	4900	6	51.00	73.20	RBEAM_400	3	125	165	-
CC3-7	4900	7	46.00	65.80	RBEAM_400	3	113	149	-
	1				-	-	-	-	





						-	-	
Client:		HOLAS KING HOMES		By:	LK	Engineer:	JLS	
Project:		CHETT WE (VISIT 2)		-21			020	
Project No.		19/0020		Date:	JUNE 20	Sheet No.	2	
Plot:	58-5	9 HT B3(A), B4(A)						
Title:	Lin	e Loads		Rev:	-	Doc. No:	226	
	ENGIN	IEERS LOADS PROVIDED BY	/ RSK REF: 133656 SK01 - SK4	18				-
Grid Reference:	Load Case	O	ther Dead	Self Weight	Total Live	Total Dead	Design SLS	Design ULS
	1	4.0	30.0	4.00	4.00	34.00	38.00	54.00
	2	2.0	37.0	4.00	2.00	41.00	43.00	60.60
	3	8.0	48.0	4.00	8.00	52.00	60.00	85.60
	4	9.0	25.0	4.00	9.00	29.00	38.00	55.00
	5	8.5	45.0	4.00	8.50	49.00	57.50	82.20
	6	9.0	38.0	4.00	9.00	42.00	51.00	73.20
	7	7.0	35.0	4.00	7.00	39.00	46.00	65.80
	8	4.0	13.0	4.00	4.00	17.00	21.00	30.20



RB Walton Park, Hearthcote Road, Swadlincote, Derbyshire DE11 9DU +44 (0)1332 977 300 • info@roger-bullivant.co.uk • www.roger-bullivant.co.uk

Client:	NICHOLAS KING HOMES	By:	LK	Eng:	JLS
Project:	MYTCHETT WE (VISIT 2)	D9:		eng:	JLO
Project No.	DH/19/0020	Date:	JUNE 20	Sheet No.	
Plot:	58-59 HT B3(A), B4(A)	Date:	JUNE 20	oneet No.	•
Title:	Beam Table	Rev:	-	Doc. No:	226

				Be	am Analysis				
Beam	Span	Load Case	Service Load (kN/m)	Ultimate Load (kN/m)	Beam Type	Minimum Section Type	Serv. Pile Rn. (kN)	Ult. Beam Rn. (kN)	Minimum Rqd. Cap Type
A1-3	1000	3	60.00	85.60	RBEAM_400	1	30	27	-
K1-1	2400	1	38.00	54.00	RBEAM_400	1	46	55	-
K1-2	2460	2	43.00	60.60	RBEAM_400	1	53	63	-
L1-2	2610	2	43.00	60.60	RBEAM_400	1	56	68	-
L1-4	2610	4	38.00	55.00	RBEAM_400	1	50	61	-
L1-5	2610	5	57.50	82.20	RBEAM_400	1	75	92	-
Q1-1	3150	1	38.00	54.00	RBEAM_400	1	60	75	-
R1-4	3360	4	38.00	55.00	RBEAM_400	1	64	82	-
R1-7	3360	7	46.00	65.80	RBEAM_400	1	77	98	-
R2-6	3360	6	51.00	73.20	RBEAM_400	2	86	109	-
T2-2	3580	2	43.00	60.60	RBEAM_400	1	77	97	-
T2-3	3610	3	60.00	85.60	RBEAM_400	2	108	138	-
T2-4	3610	4	38.00	55.00	RBEAM_400	1	69	89	-
T2-5	3580	5	57.50	82.20	RBEAM_400	2	103	132	-
T2-8	3580	8	21.00	30.20	RBEAM_400	1	38	48	-
U2-1	3730	1	38.00	54.00	RBEAM_400	1	71	90	-
U2-2	3730	2	43.00	60.60	RBEAM_400	2	80	102	-
CC3-4	4900	4	38.00	55.00	RBEAM_400	3	93	124	-
CC3-6	4900	6	51.00	73.20	RBEAM_400	3	125	165	-
CC3-7	4900	7	46.00	65.80	RBEAM_400	3	113	149	-
			-				-		



RB Walton Park, Hearthcote Road, Swadlincote, Derbyshire DE11 9DU +44 (0)1332 977 300 • info@roger-bullivant.co.uk • www.roger-bullivant.co.uk

Client:	NICHOLAS KING HOMES	By:	LK	Eng:	JLS
Project:	MYTCHETT WE (VISIT 2)	Uy.		ung.	JLO
Project No.	DH/19/0020	Date:	JUNE 20	Sheet No.	
Plot:	58-59 HT B3(A), B4(A)	Date:	JUNE 20	oneeriuo.	5
Title:	Pile Table	Rev:	-	Doc. No:	226

PILE SIZE 200 sq 250 sq - sq MAXIMUM PILE LOAD 200 kN 350 kN - kN

						Р	ILE LOAD	s					
Pile			_	Load	Case				Add.	Equalis	ed with	TOTA	L (kN)
No.	Bm	Rn	Bm	Rn	Bm	Rn	Bm	Rn	Load	Pile	Adj.	TOTA	L (KN)
4	Q1-1	60	K1-1	46	T2-4	69						174	175
5	K1-1	46	U2-1	71	T2-4	69						185	200
6	U2-1	71	T2-3	108								179	200
7	L1-2	56	T2-2	77	R1-4	64						197	200
8	R1-4	64	T2-8	38	CC3-4	93						195	200
9	CC3-4	93	T2-5	103	L1-5	75						271	275
10	T2-4	69	L1-4	50								118	125
11	T2-4	69	T2-4	69								137	150
12	T2-3	108	T2-3	108								217	225
13	R1-7	77	L1-2	56								133	150
14	CC3-7	113	R1-7	77								190	200
15	Q1-1	60	CC3-7	113	L1-5	75						248	250
16	Q1-1	60	A1-3	30	L1-4	50						139	150
17	K1-2	53	A1-3	30								83	100
18	U2-2	80	K1-2	53	T2-4	69						202	225
19	T2-3	108	U2-2	80								188	200

 Project Name
 MYTCHETT\_WE\_(VISIT\_2),
 Plot Ref.
 58-59

 Client
 NICHOLAS KING HOMES,
 Project No.
 DH 19 0020

	leference	Easting (m)	Northing (m)		^		Pile No.	Easting (m)	Northing (m)	<u>^</u>	
A		100.000	200.000	9			1	100.163	206.357		
В		100.000	206.520	₽			2	103.525	206.357		
С		108.425	206.520	Г			3	108.425	206.357		( Cond Drawing D
D		117.880	206.520	Г			4	111.579	206.357		< Load Drawing D
Е		117.880	198.998	Г			5	113.985	206.357		Export Site Data
F		111.361	198.998	Г			6	117.717	206.357		Export one bat
G		111.361	199.999	Г			7	100.163	202.775		Import As Built Da
Н		108.425	200.000	Г			8	103.525	202.775		
							9	108.425	202.775		Print
							10	111.578	202.775		
							11	113.985	202.775		Save
							12	117.717	202.775		
							13	100.163	200.163		Exit
							14	103.525	200.163		
							15	108.425	200.163		Date Site Create
							16	111.551	200.163		
							17	111.524	199.161		09/09/2021
							18	113.984	199.161		Date of Source Da
						-	19	117.717	199.161		21/07/2020
					~					~	Progress





Client:	NICI	HOLAS KING HOMES		By:	LK	Engineer:	JLS			
Project:	MYT	CHETT WE (VISIT 2)		by.	LN	Engineer.	JLS	320		
Project No.		19/0020		Date:	JUNE 20	Sheet No.	2			
Plot:	58-5	9 HT B3(A), B4(A)								
Title:	Lin	e Loads		Rev:	-	Doc. No:	226			
	ENGIN	EERS LOADS PROVIDED B	Y RSK REF: 133656 SK01 - \$	SK48						
Grid Reference:	Load Case	O	ther Dead	Self Weight	Total Live	Total Dead	Design SLS	Desigr ULS		
	1	4.0	30.0	4.00	4.00	34.00	38.00	54.00		
	2	2.0	37.0	4.00	2.00	41.00	43.00	60.60		
	3	8.0	48.0	4.00	8.00	52.00	60.00	85.60		
	4	9.0	25.0	4.00	9.00	29.00	38.00	55.00		
	5	8.5	45.0	4.00	8.50	49.00	57.50	82.20		
	6	9.0	38.0	4.00	9.00	42.00	51.00	73.20		
	7	7.0	35.0	4.00	7.00	39.00	46.00	65.80		
	8	4.0	13.0	4.00	4.00	17.00	21.00	30.20		
		4.0	10.0	4.00	7.00	11.00	21.00	30.20		



RB Walton Park, Hearthcote Road, Swadlincote, Derbyshire DE11 9DU +44 (0)1332 977 300 • info@roger-bullivant.co.uk • www.roger-bullivant.co.uk

Client:	NICHOLAS KING HOMES	By:	LK	Eng:	JLS
Project:	MYTCHETT WE (VISIT 2)	C.y.	LIX	ung.	31.5
Project No.	DH/19/0020	Date:	JUNE 20	Sheet No.	
Plot:	58-59 HT B3(A), B4(A)	Date:	JUNE 20	oneet No.	*
Title:	Beam Table	Rev:	-	Doc. No:	226

				Be	am Analysis				
Beam	Span	Load Case	Service Load (kN/m)	Ultimate Load (kN/m)	Beam Type	Minimum Section Type	Serv. Pile Rn. (kN)	Ult. Beam Rn. (kN)	Minimum Rqd. Cap Type
A1-3	1000	3	60.00	85.60	RBEAM_400	1	30	27	-
K1-1	2400	1	38.00	54.00	RBEAM_400	1	46	55	-
K1-2	2460	2	43.00	60.60	RBEAM_400	1	53	63	-
L1-2	2610	2	43.00	60.60	RBEAM_400	1	56	68	-
L1-4	2610	4	38.00	55.00	RBEAM_400	1	50	61	-
L1-5	2610	5	57.50	82.20	RBEAM_400	1	75	92	-
Q1-1	3150	1	38.00	54.00	RBEAM_400	1	60	75	-
R1-4	3360	4	38.00	55.00	RBEAM_400	1	64	82	-
R1-7	3360	7	46.00	65.80	RBEAM_400	1	77	98	-
R2-6	3360	6	51.00	73.20	RBEAM_400	2	86	109	-
T2-2	3580	2	43.00	60.60	RBEAM_400	1	77	97	-
T2-3	3610	3	60.00	85.60	RBEAM_400	2	108	138	-
T2-4	3610	4	38.00	55.00	RBEAM_400	1	69	89	-
T2-5	3580	5	57.50	82.20	RBEAM_400	2	103	132	-
T2-8	3580	8	21.00	30.20	RBEAM_400	1	38	48	-
U2-1	3730	1	38.00	54.00	RBEAM_400	1	71	90	-
U2-2	3730	2	43.00	60.60	RBEAM_400	2	80	102	-
CC3-4	4900	4	38.00	55.00	RBEAM_400	3	93	124	-
CC3-6	4900	6	51.00	73.20	RBEAM_400	3	125	165	-
CC3-7	4900	7	46.00	65.80	RBEAM_400	3	113	149	-
	1								



₿	RB Walton Park, Hearthcote Road, Swadlinc +44 (0)1332 977 300 • info@roger-bullivant.co.u				
Client:	NICHOLAS KING HOMES	Bu:	LK	Eng:	JLS
Project:	MYTCHETT WE (VISIT 2)	by:		Elly:	JLS
Project No.	DH/19/0020			Sheet No.	
Plot:	58-59 HT B3(A), B4(A)	Date:	JUNE 20	Sheet No.	5
Title:	Pile Table	Rev:	-	Doc. No:	226

PILE SIZE MAXIMUM PILE LOAD 200 sq 250 sq 350 kN - sq - kN 200 kN

						P	ILE LOAD	S					
Pile				Load	Case				Add.	Equalis	ed with	TOTA	
No.	Bm	Rn	Bm	Rn	Bm	Rn	Bm	Rn	Load	Pile	Adj.	TOTA	L (kN)
4	Q1-1	60	K1-1	46	T2-4	69						174	175
5	K1-1	46	U2-1	71	T2-4	69						185	200
6	U2-1	71	T2-3	108								179	200
7	L1-2	56	T2-2	77	R1-4	64						197	200
8	R1-4	64	T2-8	38	CC3-4	93						195	200
9	CC3-4	93	T2-5	103	L1-5	75						271	275
10	T2-4	69	L1-4	50								118	125
11	T2-4	69	T2-4	69								137	150
12	T2-3	108	T2-3	108								217	225
13	R1-7	77	L1-2	56								133	150
14	CC3-7	113	R1-7	77								190	200
15	Q1-1	60	CC3-7	113	L1-5	75						248	250
16	Q1-1	60	A1-3	30	L1-4	50						139	150
17	K1-2	53	A1-3	30								83	100
18	U2-2	80	K1-2	53	T2-4	69						202	225
19	T2-3	108	U2-2	80								188	200
									1				

As Built F	Pile Co-Ordinate	s			
Pile No.	Easting (m)	Northing (m)	Difference Easting (mm)	Difference Northing (mm) 🔺	
1	488742.384	154732.963	43	6	
2	488745.732	154733.102	55	39	
3	488750.652	154733.162	33	38	< Load Drawing
4	488753.867	154733.284	29	5	C Load Drawing
5	488756.867	154733.432	624	76	Export Site D
6	488759.953	154733.498	21	38	
7	488742.515	154729.332	12	56	Import As Built
8	488745.901	154729.495	13	13	
9	488750.757	154729.575	29	45	Print AsBuil
10	488753.927	154729.688	10	20	Save
11	488756.315	154729.787	28	12	Save
12	488760.061	154729.931	13	51	Exit
13	488742.617	154726.760	17	17	Exit
14	488745.976	154726.856	15	15	
15	488750.842	154726.988	17	21	Date Site Cre-
16	488753.958	154727.065	26	31	20/05/2021
17	488753.980	154726.071	5	23	Date of Source
18	488756.442	154726.130	2	33	21/07/20
19	488760.194	154726.235	19	32	
- ···				~	Progress

Site L	ocation	Co-Ordinat	tes 🚫	R	2	Si	te Pile C	o-Ordinates		0	
Re	ference	Easting (m)	Northing (m)		^		Pile No.	Easting (m)	Northing (m)	^	
ÞΑ		100.000	200.000	4			1	100.163	206.357		360 280
В		100.000	206.520	V			2	103.525	206.357		
С		108.425	206.520	Г			3	108.425	206.357		< Load Drawin
D		117.880	206.520	Г			4	111.579	206.357		Load Drawin
E		117.880	198.998	Г			5	113.985	206.357		Export Site D
F		111.361	198.998	Г			6	117.717	206.357		Export site E
G		111.361	199.999	Г			7	100.163	202.775		Import As Built
H		108.425	200.000	Г			8	103.525	202.775		
							9	108.425	202.775		Print
							10	111.578	202.775		
							11	113.985	202.775		Save
							12	117.717	202.775		
							13	100.163	200.163		Exit
							14	103.525	200.163		
							15	108.425	200.163		Date Site Cre
							16	111.551	200.163		09/09/2021
							17	111.524	199.161		03/03/2021
							18	113.984	199.161		Date of Source
							19	117.717	199.161		21/07/20
					~					~	Progress
					~	ľ	13	10.00	133,161	<b>,</b>	





			e megreger samanare.					
Client:		HOLAS KING HOMES		By:	LK	Engineer:	JLS	
Project:		CHETT WE (VISIT 2)		by.		Engineer.	320	
Project No.		19/0020		Date:	JUNE 20	Sheet No.	2	
Plot	58-5	9 HT B3(A), B4(A)						
Title:	Lin	e Loads		Rev:		Doc. No:	226	
1	ENGIN	IEERS LOADS PROVIDED BY	/ RSK REF: 133656 SK01 - SK4	8				
Grid Reference:	Load Case		ther	Self Weight	Total Live	Total Dead	Design SLS	Design ULS
		Live	Dead					
	1	4.0	30.0	4.00	4.00	34.00	38.00	54.00
	2	2.0	37.0	4.00	2.00	41.00	43.00	60.60
	3	8.0	48.0	4.00	8.00	52.00	60.00	85.60
	4	9.0	25.0	4.00	9.00	29.00	38.00	55.00
	5	8.5	45.0	4.00	8.50	49.00	57.50	82.20
	6		22.0	4.00	9.00	42.00	51.00	73.20
	•	9.0	38.0	4.00	5.00	42.00	51.00	13.20
	7	9.0 7.0	38.0	4.00	7.00	39.00	46.00	65.80



RB Walton Park, Hearthcote Road, Swadlincote, Derbyshire DE11 9DU +44 (0)1332 977 300 • info@roger-bullivant.co.uk • www.roger-bullivant.co.uk

Client:	NICHOLAS KING HOMES	Be	LK	Eng:	JLS
Project:	MYTCHETT WE (VISIT 2)	Dy.	LK	Eng:	JLS
Project No.	DH/19/0020	Date:	JUNE 20	Sheet No.	
Plot:	58-59 HT B3(A), B4(A)	Date:	JUNE 20	oneer No.	•
Title:	Beam Table	Rev:	-	Doc. No:	226

				Be	am Analysis				
Beam	Span	Load Case	Service Load (kN/m)	Ultimate Load (kN/m)	Beam Type	Minimum Section Type	Serv. Pile Rn. (kN)	Ult. Beam Rn. (kN)	Minimum Rqd. Cap Type
A1-3	1000	3	60.00	85.60	RBEAM_400	1	30	27	-
K1-1	2400	1	38.00	54.00	RBEAM_400	1	46	55	-
K1-2	2460	2	43.00	60.60	RBEAM_400	1	53	63	-
L1-2	2610	2	43.00	60.60	RBEAM_400	1	56	68	-
L1-4	2610	4	38.00	55.00	RBEAM_400	1	50	61	-
L1-5	2610	5	57.50	82.20	RBEAM_400	1	75	92	-
Q1-1	3150	1	38.00	54.00	RBEAM_400	1	60	75	-
R1-4	3360	4	38.00	55.00	RBEAM_400	1	64	82	-
R1-7	3360	7	46.00	65.80	RBEAM_400	1	77	98	-
R2-6	3360	6	51.00	73.20	RBEAM_400	2	86	109	-
T2-2	3580	2	43.00	60.60	RBEAM_400	1	77	97	-
T2-3	3610	3	60.00	85.60	RBEAM_400	2	108	138	-
T2-4	3610	4	38.00	55.00	RBEAM_400	1	69	89	-
T2-5	3580	5	57.50	82.20	RBEAM_400	2	103	132	-
T2-8	3580	8	21.00	30.20	RBEAM_400	1	38	48	-
U2-1	3730	1	38.00	54.00	RBEAM_400	1	71	90	-
U2-2	3730	2	43.00	60.60	RBEAM_400	2	80	102	-
CC3-4	4900	4	38.00	55.00	RBEAM_400	3	93	124	-
CC3-6	4900	6	51.00	73.20	RBEAM_400	3	125	165	-
CC3-7	4900	7	46.00	65.80	RBEAM_400	3	113	149	-
	1	1				1			1



PILE SIZE

Client

RB Walton Park, Hearthcote Road, Swadlincote, Derbyshire DE11 9DU +44 (0)1332 977 300 • info@roger-bullivant.co.uk • www.roger-bullivant.co.uk

Client:	NICHOLAS KING HOMES	By:		Ena:	JLS
Project:	MYTCHETT WE (VISIT 2)	uy.	LIX	ung.	JLO
Project No.	DH/19/0020	Date:	JUNE 20	Sheet No.	5
Plot:	58-59 HT B3(A), B4(A)	Date:	JUNE 20	oneer rao.	5
Title:	Pile Table	Rev:	-	Doc. No:	226

250 sq 200 sq - sq - kN MAXIMUM PILE LOAD 200 350 kN kN

[							P	ILE LOAD	s					
	Pile			_	Load	Case				Add.	Equalis	ed with	TOTA	L (kN)
	No.	Bm	Rn	Bm	Rn	Bm	Rn	Bm	Rn	Load	Pile	Adj.	IUIA	L (KN)
	4	Q1-1	60	K1-1	46	T2-4	69						174	175
	5	K1-1	46	U2-1	71	T2-4	69						185	200
	6	U2-1	71	T2-3	108								179	200
	7	L1-2	56	T2-2	77	R1-4	64						197	200
	8	R1-4	64	T2-8	38	CC3-4	93						195	200
	9	CC3-4	93	T2-5	103	L1-5	75						271	275
	10	T2-4	69	L1-4	50								118	125
	11	T2-4	69	T2-4	69								137	150
	12	T2-3	108	T2-3	108								217	225
	13	R1-7	77	L1-2	56								133	150
	14	CC3-7	113	R1-7	77								190	200
	15	Q1-1	60	CC3-7	113	L1-5	75						248	250
	16	Q1-1	60	A1-3	30	L1-4	50						139	150
	17	K1-2	53	A1-3	30								83	100
	18	U2-2	80	K1-2	53	T2-4	69						202	225
	19	T2-3	108	U2-2	80								188	200
						1				1	1	i i	1	

Project Name MYTCHETT\_WE\_(VISIT\_2), Plot Ref. 58-59 NICHOLAS KING HOMES,

Project No. DH 19 0020

Dra	awing Data S	Site Data 🛛 As Bui	lt Site Data   Ne	wΑ	utoCa	AD E	Data				
S	ite Locatio	n Co-Ordinat	es 🔕	í.	3	S	ite Pile C	o-Ordinates		0	
Г	Reference	Easting (m)	Northing (m)		^	Г	Pile No.	Easting (m)	Northing (m)	^	
Þ	A	100.000	200.000	1		∣₽	1	100.163	206.357		
	В	100.000	206.520	1			2	103.525	206.357		
	С	108.425	206.520	<u>Ч</u> П			3	108.425	206.357		
	D	117.880	206.520	Γ			4	111.579	206.357		< Load Drawing Data
	E	117.880	198.998	Г			5	113.985	206.357		Export Site Data
	F	111.361	198.998				6	117.717	206.357		Export site bata
	G	111.361	199.999	Г			7	100.163	202.775		Import As Built Data
	Н	108.425	200.000	Г			8	103.525	202.775		Importivio balle balla
							9	108.425	202.775		Print
							10	111.578	202.775		
					-		11	113.985	202.775		Save
							12	117.717	202.775		
							13	100.163	200.163		Exit
							14	103.525	200.163		
							15	108.425	200.163		Date Site Created
							16	111.551	200.163		
							17	111.524	199.161		09/09/2021 💌
							18	113.984	199.161		Date of Source Data
							19	117.717	199.161		21/07/2020
											LIVOIVEOED
					~					×	Progress
-					-	-	_				
		TEODD -						N ITS			
		RTFORD						NR			
No	one							Design Er	ngineer lewis.	.king	

	E 11 1 3	hu av ka			
Pile No.	Easting (m)	Northing (m)	Difference Easting (mm)	Difference Northing (mm)	
▶ 1	488742.384	154732.963	43	6	- Charles
2	488745.732	154733.102	55	39	
3	488750.652	154733.162	33	38	< Load Drawing D
4	488753.867	154733.284	29	5	
5	488756.867	154733.432	624	76	Export Site Data
6	488759.953	154733.498	21	38	
7	488742.515	154729.332	12	56	Import As Built Da
8	488745.901	154729.495	13	13	Print AsBuilt
9	488750.757	154729.575	29	45	Print Asbuit
10	488753.927	154729.688	10	20	Save
11	488756.315	154729.787	28	12	
12	488760.061	154729.931	13	51	Exit
13	488742.617	154726.760	17	17	
14	488745.976	154726.856	15	15	Date Site Create
15	488750.842	154726.988	17	21	
16	488753.958	154727.065	26	31	20/05/2021
17	488753.980	154726.071	5	23	Date of Source D
	488756.442	154726.130	2	33	21/07/2020
18	488760.194	154726.235	19	32	

Plot Ref. 58-59



Project Name MYTCHETT\_WE\_(VISIT\_2),

RB Walton Park, Hearthcote Road, Swadlincote, Derbyshire DE11 9DU +44 (0)1332 977 300 • info@roger-bullivant.co.uk • www.roger-bullivant.co.uk

V			oyrooz orr coo o nirolarogor	bailitant.co.an		oger ban	in an a solution			
Client:		NICHOLAS	KING HOMES	By:	JLS	Engineer:	JLS	í		 ח
Project:		MYTCHETT	WE (VISIT 2)	Date:	21/05/21	Sheet No.		Pile Size	200	I
Project N	lo.	DH/19/0020		Checked:		Date:				ľ
Plot:		58-59 HT B	3(A), B4(A)	Approved:		Date:		r		5
Out Of	Position Pil	les:	Refer to Roger Bullivant Ltd. Dr	awings Ref:	DH/19/002	20/265				
Nos.	13No. Pile	s <50mm out	5No. Piles 50-75mm out	1No. Pil	es >75mm	out	19No. Pi	es Total		
										-

Pile No.	Pile Load (See Drg.) (kN)	Amount Out Of Position (mm)	Service Moment (kNm)	Out Of Position Diagram Ref. No.	Moment reduction due to drop in steel	Manual reduction in moment, due to pile location	Net moment in pile	Allowable moment in pile	Comment
1	163	43	7.0		0.0		7.0		NO ACTION REQUIRED
2	248	68	16.9	2	18.0		0.0		ENSURE BEARING
3	288	51	14.7		0.0		14.7		NO ACTION REQUIRED
4	174	30	5.2		0.0		5.2		NO ACTION REQUIRED
		629	116.4		0.0		116.4		REMEDIAL ACTION REQUIRED
6	179	42	7.5		0.0		7.5		NO ACTION REQUIRED
7	197	58	11.4		0.0		11.4		NO ACTION REQUIRED
8	195	18	3.5		0.0		3.5		NO ACTION REQUIRED
9	271	53	14.4		0.0		14.4		NO ACTION REQUIRED
10	118	23	2.7		0.0		2.7		NO ACTION REQUIRED
11	137	30	4.1		0.0		4.1		NO ACTION REQUIRED
12	217	52	11.3		0.0		11.3		NO ACTION REQUIRED
13	133	24	3.2		0.0		3.2		NO ACTION REQUIRED
14	190	22	4.2		0.0		4.2		NO ACTION REQUIRED
15	248	28	6.9		0.0		6.9		NO ACTION REQUIRED
16	139	41	5.7		0.0		5.7		NO ACTION REQUIRED
17	83	24	2.0		0.0		2.0		NO ACTION REQUIRED



NO ACTION REQUIRED NO ACTION REQUIRED

les					<b></b>
	ile Type			Pile Qu	-
R 200 SQ PRECAST	ſ			1	3
R 250 SQ PRECAST	1			6	;
aps					<b></b>
c	ар Туре			Cap Qu	iantity
В				1	2
BIG B				1	
D				4	•
BIG D				2	2
situ					<b></b>
		Standar	d Cages		
Quantity	1	Ту	pe		Length (m)
		Total Insitu	Volume (m <sup>3</sup> )		
Mes	h / Dowels	;		Quar	ntity
ams					<b></b>
Beam Group	Beam	n Grid Length (m)	Beam Conc Lo (m)	ength	Beam Weight (t)
RTIE		9.49	9		1.170
RBEAM400		80.87	77.25		22.342
p Steel					<b></b>
В	ar Mark		Ba	ar Mark	Quantity
01				7	1
02				1	5
03				3	•
04				3	1
07				1	
08				1	
ickers					<b></b>
Packer Typ	be	Packer	Depth	F	acker Quantity
390W		1	75		12
390W		1	50		21
eave Precautions					<b></b>
	Туре			Quanti	ty (m)



011				ROGER BU	LLIVANT Ltd						SHEET 1 OF 1											_					
Piles	<b>T</b>	D11- 0	▲ ·	noutribo		oom /1	nn Cohodi	la (Qtr	ock Lengths)	1	JILLITOT			www.roger-b	ullivant.co.u	k	CLIENT:	NICHOLAS I	KING HOMES		SHEET	No: 5					
	Туре		lantity			5aiii 40	DESIGN DE		-		DC CLA	66	V				PROJEC		WE (VISIT 2)			ATE: 22/07/20					
R 200 SQ PRECAST			3				DEGIUN DE				DC-3			OUNDATIONS		PARTMENT	JOB No.	DH/19/0020			REVISIO	ON:					
R 250 SQ PRECAST			5		DH 19 00			DATE:-	22/07/20 Boy		00-0		MATERIA	L SCHEDULE			REGION	RB SOUTH E	EAST								_
Caps			<b></b>	Project :- Plot Ref :-	MYTCHE 58-59	II_WE_	(VISI1_2)		Rev.					PLES	DI E CADS	STANDARD CAG	20		AST BEAM (CONCRETE)	Der	PSTL	ette	P STEEL	DESCRIPTION	A383	INSITU	BY
Сар	Туре	Cap Qu	Jantity																	RBeam					MESH MESH	CONC. VOLUME TYPE	
В		1	2	BEAM Code /Type		QTY	COMMENTS / Drawing No.	Wt. Each	BEAM CO Code/Type L	NCRETE QTY ENGTH	COMMENTS / Drawing No.	Wt. Each	PLOT REF.	No. TYPE N	o. TYPE	No. TYPE LEN	GTH 450R	(m) (m) (n)	Tie T5 RBeam	RTie 400 Mk.	Mk Mk	Ak Mk Mk	Mk Mk M	ik Mk Mk	BARS % Sheet	(m <sup>3</sup> )	75mm 150
BIG B		· ·	I			4	Drawing No.		Code/Type Li	ENGTH	Drawing No.	Each	36	18	в		9.2	(in) (in) (i	<u>, (iii) (iii)</u>	10.4 41.0 3	6 2	4 2 2	3 1	3	10.0	1.89 390W	N 10 2
D		4	ł	A 1 K 1	900 2250	1		0.18				_		1 2 3	BIG B											440W	N 1 2
BIG D		2	2	L1	2400	3		0.62							B800HD					'	$\square$	++	+++	+++			++
Insitu			<b></b>	Q 1	3000	2		0.80							· ·		_			15.6	<u>.                                    </u>	++-	+++	+++			+++-
	Standar	rd Cages		R 1 R 2	3150 3150	2	+	0.85					36g 37-38	4 4	1 B		13.0		+	15.6 83 552 6	8 2	5 6 7			13 15.5		N 4 N 2 23
Quantity		ype	Length (m)	T2	3150	1	+	0.85					37-30	6 1 3	2 D		13.9		+++	0.0 0.2 0		3 0 2			10 10.0		N 2 1
quantity	-	Volume (m <sup>3</sup> )	congur (m)	U 2	3600	2		0.99							BIG D												
			- 124 -	CC 3	4800	3		<u>1.68</u>							2 D800HD												
-	Dowels	Qua	ntity	L	2400	1	TIE	0.31				_	47-52	~ `	B	3 SD 1.				17.4 75.2 20	14 3	6 3 2	2	2 8	14.0		
Beams			▲	U	3000 3600	1	TIE	0.39				_			BIG D	4 SD 1.						++	+++	+++		440W	N 4
Beam Group	Beam Grid Length	Beam Conc Length	Beam Weight (t)		0000	<u> </u>	112	0.47					53-55		2 B	1 HU 1.	14.8			20.3 96.8 10	16 7	12	3	1 1	12.0	3.79 390W	N 10
•	(m)	(m)													L D		1.0				Ă.	+-		+++		440W	
RTIE	9.49	9	1.170									_			B D800HD												
RBEAM400	80.87	77.25	22.342										56-57							4.8 72.2 5	14 6	2	$\downarrow$	$\downarrow$		390W	N 14
Top Steel			<b></b>											<u> </u>	i D L BIGD					<u> </u>		++-	+++	+++			+
Bar	Mark	Bar Mark	Quantity										58-59		BIGD					9.0 77.3 7	15 3	3	1 1	+++		3004	N 12 2
01		1	7			-						_		6 1	BIGB				++++		Ť	+	++++	+++			
02		1	5												D												
03			3											;	BIG D						$\square$						
04			3	_									60-62		B		_			27.0 81.9 12	9 7	1 3	3	2 1	2.0	0.82 390W	/ 17 3
07						-						_			BIG B		_		++++	$\rightarrow$	$\vdash$	++	+++	+++			+++
08															BIGD				++++			++-	+++	+++		$\square$	+++
		1	•		90.36	GRID LE	ENGTH (m)	T																			
Packers Packer Type	Dealer	r Depth	Packer Quantity	SUMM	ARY			<u>w</u>	EIGHT																		
				Type 1	<u>No.</u> 10	LENGTH 24.90	H (MTRS)	6.50			RB400 & RTIE		TOTAL					0 0 0	0 0 0	97 515 69	95 33	21 31 7	9 8	ŝ 2 18	14 54	18.76	101 1
390W		75	12	Type 2	11	24.90 37.95 14.40	62.85	6.50 10.37	16.88	TOTAL Qty	27			REY TO	TAL CAP CAGE	9:	NOTES:			len	HEDULED	BV.				NCRETE DC CL	ASS REO
390W		150	21	Type 3 Type 4		14.40	14.40	5.04	5.04	TOTAL Mtr	a. 86.25			Q PCC +							LUULED				-		
Hanna Danaantiana			<b>A</b>	Туре 5	TOTAL RB40	0	77.25	ł	21.92														wis King		_		
Heave Precautions						-	11.20	t	A 1.92	TOTAL IN	00.00									CHF	ECKED BY	£				DC 2/	
Heave Precautions Ty	/ре	Quant	ity (m)	RTIE	3		9.00	RTIE	1.17	TOTAL WI	. 23.09 (Tonnes)												sit.	-		DC-3 (F	TNDJ





State State State


-----


PROPERTY AND NOT AND ADDRESS OF TAXABLE PARTY OF TAXABLE PARTY.

De













Cito nt Project Project Pisot	MYTCHE No. DH/19/00	AS KING HOMES TT WE (VISIT 2) 20 B3(A), B4(A)	By: Date: Checked: Approved.	LK JUNE 20	Engineer Shoet No. Date: Date:	JLS 1 15/07/20 21/7/20	
Tibe		CT CALCULATIONS	Pare:	- IEIA	Doc. No:	226	
	Revision D	escription		Date	Initials	Checked	
							•











## Roger Bullivant – lessons learnt

Site investigation – sufficient and detailed appropriate for the site with boreholes to areas to significant depth minimum 3.0 to 5.0m below estimated depth of pile.

Knowledge of any remediation or any environmental issues to ensure details are taken into consideration

Preparation works – any cut and fill, and method of installing the 'working platform' that could have an affect on the works ahead.

Receipt of relevant Construction drawings, Engineering layouts at an early stage to enable a relevant estimate to be submitted. (Changes to design during this process can lead to additional abortive charges)

The 'working platform' is at minimum soffit of the Precast beam.

LAST is to have dialogue with your customer and where possible the Design team to understand the project, their expectations and what we can provide.





#### **Presentations**

#### **Upcoming**

- Offsite Manufacturing On Site Piling
- The Completed Solution

#### www.roger-bullivant.co.uk/webinars-2




Thank you for listening! We will now move onto a Q&A, followed by a survey.

All questions are welcome!

# www.roger-bullivant.co.uk

☑ Info@roger-bullivant.co.uk



@rogerbullivantlimited

